



**BOONE COUNTY, MISSOURI**  
**Request for Bid # 07-13MAR08-Marshall Lane Bridge Project, Riley Road Bridge Project**  
**& Rolling Hills Road Bridge Project**


**ADDENDUM #1 - Issued March 11, 2008**

This addendum is issued in accordance with the Request for Bid and is hereby incorporated into and made a part of the Request for Bid Documents. Bidders are reminded that receipt of this addendum *should* be acknowledged and submitted with Offeror's *Revised Bid Form and related submittals*.

Specifications for the above noted Request for Bid and the work covered thereby are herein modified as follows, and except as set forth herein, otherwise remain unchanged and in full force and effect:

1. Add section 1.1.4 under SUMMARY OF WORK on page 15.2.  
Marshall Lane – Galvanized tin shall be used to replace the cattle panel specified for the water gap.
2. Add section 1.2.4 under SUMMARY OF WORK on page 15.2  
Riley Road – All structural steel materials, including the sheet piling and channel rail, used on this project shall be new or used and in good condition. The materials shall meet Boone County's approval prior to installation.
3. Add section 1.3.2 under SUMMARY OF WORK on page 15.2  
Rolling Hills Road - The concrete abutment protection lining shall extend 9" above the degraded portion of the existing abutment wall regardless of the level of water at the time of construction.

By:

  
**Tyson Boldan,**  
**Buyer**

OFFEROR has examined copy of Addendum #1 to Request for Bid # 07-13MAR08 – **Marshall Lane Bridge Project, Riley Road Bridge Project & Rolling Hills Road Bridge Project**, receipt of which is hereby acknowledged:

Company Name: \_\_\_\_\_  
Address: \_\_\_\_\_  
\_\_\_\_\_

Phone Number: \_\_\_\_\_ Fax Number: \_\_\_\_\_

Authorized Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

Authorized Representative Printed Name: \_\_\_\_\_