

**ADDENDUM # 2
BOONE COUNTY, MISSOURI
LLOYDE HUDSON ROAD LOW WATER CROSSING
BID NO: 33-10JUL08**

ADDENDUM # 2

This addendum is issued in accordance with the Instruction to Bidders and hereby incorporated into and made a part of the Contract Documents.

Bidders are reminded that receipt of this addendum must be acknowledged and submitted with the attached Acknowledgment of Addendum Form and attached to your Bid Form.

Drawings and specifications for the above noted project and the work covered thereby are herein modified as follows, and except as set forth herein, otherwise remain unchanged and in full force and effect:

PROJECT REVISIONS / CLARIFICATIONS

- 1. Please omit page 6 of 9 of the plan sheets. The design, installation and the maintenance of the temporary by-pass is solely the responsibility of the contractor.**
- 2. The one year performance bond in the amount of 1.5 times the total cost of the restoration and erosion control fabric(s) as described in the second paragraph of the Maintenance Requirements on page 10.5 of the specifications will not be required and should be disregarded.**
- 3. Two 36" X 42.5' 14 gauge Aluminized culvert have been approved to be used for this project as an alternate to the two 36" X 42.5' 14 gauge Polycoated culvert**
- 4. All culvert must be annular riveted as per Boone County specifications**
- 5. The Bid Tab quantity for Rock Excavation will be increased from 1 CY to 10 CY. A revised Bid Tab has been attached and should be used for bidding purposes.**
- 6. Replace existing Bid Form with the attached Revised Bid Form**

ADDENDUM # 2
BOONE COUNTY, MISSOURI
LLOYDE HUDSON ROAD LOW WATER CROSSING
BID NO: 33-10JUL08

Lloyd Hudson Road Low Water Crossing Project					
	Description	Quantity	Unit	Unit Price	Extended Total
1-1.	Mobilization	1	LS		
1-2.	Traffic Control	1	LS		
1-3.	Removals	1	LS		
1-4.	Excavation	42	CY		
1-5.	Embankment	42	CY		
1-6.	1.5" Minus Base Rock	190	TON		
1-7.	Class A Portland Cement Concrete	80	CY		
1-8.	Type 1 Rolled Stone Base Rock	69	TON		
1-9.	Tensar BX 1100 Geogrid	389	SY		
1-10.	Reinforcing Steel (Including Tie Bars)	2170	LBS		
1-11.	Type 2 Rock Blanket (24" deep)	74	CY		
1-12.	Field Seeding/Fertilizing/Mulching	1	LS		
1-13.	36" Polycoated CMP's 14 gauge	85	LF		
1-14.	Temporary Bypass	1	LS		
1-15.	Geotex 315ST	389	SY		
1-16.	Construction Staking	1	LS		
1-17.	Rock Excavation	10	CY		
				TOTAL:	

ADDENDUM # 2
BOONE COUNTY, MISSOURI
LLOYDE HUDSON ROAD LOW WATER CROSSING
BID NO: 33-10JUL08

BIDDER has examined copies of all the Bidding Documents and of the following Addenda (receipt of all which is hereby acknowledged):

<u>DATE</u>	<u>ADDENDUM NUMBER</u>
<hr/>	
<hr/>	
COMPANY NAME:	<hr/>
ADDRESS:	<hr/>
PHONE NUMBER:	<hr/>
AUTHORIZED REPRESENTATIVE:	<hr/>
	<hr/>