

# ALLEN INVESTMENT HOLDINGS, LLC 700 FAY ST..

### COLUMBIA, MISSOURI 65201

- WATER DISTRIBUTION TO BE PROVIDED BY CONSOLIDATED WATER DISTRICT #1.
- AN EXISTING SANITARY SEWER FORCE MAIN EXISTS NEAR THE NORTHWEST CORNER OF THIS PROPERTY. THIS DEVELOPMENT WILL CONNECT TO THAT SEWER AND HAS SEWER CAPACITY PURCHASED.
- THE EXISTING ZONING OF THIS TRACT IS M-LP.
- 4. THIS TRACT CONTAINS 11.23 ACRES.
- ELECTRIC DISTRIBUTION PROVIDED BY BOONE ELECTRIC.
- 6. THERE SHALL BE A 25' PERIMETER SETBACK ALONG ALL SIDES OF THIS TRACT.
- THE MAXIMUM HEIGHT OF ANY BUILDING WILL NOT EXCEED 40'.
- 8. THIS TRACT IS SUBJECT TO THE BOONE COUNTY STORMWATER ORDINANCE.
- 9. THE DRIVEWAY CONNECTION TO TOM BASS ROAD HAS BEEN APPROVED BY MODOT.
- 10. ALL SIGNAGE SHALL CONFORM TO BOONE COUNTY ZONING REGULATIONS.
- EXISTING UTILITIES. SITE FEATURES. AND MISCELLANEOUS COMPONENTS MAY BE REMOVED. REPLACED, UPGRADED, & ADDED AS DETAILED DESIGN PROGRESSES IN THE DEVELOPMENT OF THE SITE PLAN AT THE DISCRETION OF THE DIRECTOR OF RESOURCE MANAGEMENT.
- 12. SQUARE FOOTAGES OF PROPOSED BUILDINGS ARE APPROXIMATE AND THE FINAL AREA MAY VARY SLIGHTLY.

# PHASING PLAN:

# THIS PROJECT SHALL BE DEVELOPED IN MULTIPLE PHASES.

THE 6,000 SQ.FT. BUILDING WITH TRUCK LOADING DOCK SHALL BE THE FIRST PHASE. THE OTHER BUILDINGS LABELED AS "FUTURE" MAY BE CONSTRUCED IN FUTURE PHASES. ANY BUILDINGS CONSTRUCTED IN THE FUTURE SHALL HAVE ADEQUATE PARKING FACILITIES CONSTRUCTED AT THE SAME TIME BASED ON THE USE OF THE ASSOCIATED BUILDINGS.

# LANDSCAPE AND BUFFERING PLAN:

THIS SHEET HAS BEEN SIGNED, SEALED AND

DATED ELECTRONICALLY

ANDREW T.


GREENE

NUMBER

A 25 FOOT PERIMETER SETBACK IS PROVIDED ALONG THE PROPERTY BOUNDARY.

THE STREAM BUFFER TO THE WEST OF THIS PROPERTY PROVIDES A SIGNIFICANT, NATURAL VEGETATIVE SCREEN AND BUFFER.

# REQUESTED ALLOWED USES:



SMALL BATCH DISTILLERY (APPROXIMATE WEEKLY PRODUCTION IS 500 GALLONS)

BAR OR TAVERN (LIMITED TO A TASTING ROOM ASSOCIATED WITH A BOTTLING WORKS WITH AN OCCUPANCY LIMITED TO 20 PATRONS TOTAL) WAREHOUSE/STORAGE (INCIDENTAL TO A DIFFERENT PRIMARY USE, WAREHOUSE/STORAGE MAY NOT BE A PRIMARY USE ON THIS SITE) EXTERIOR STORAGE AREAS (SHIPPING CONTAINERS STORING FINISHED PRODUCT, PROTECTED FROM SPILLAGE DIRECTLY INTO THE ENVIRONMENT)

| 10/20/2022                   |   |
|------------------------------|---|
| ANDREW T. GREENE, 2020000043 | APPROVED BY THE BOONE COUNTY COMMISSION |
| ) BV·                        | THIS, 20                                |

CRUCKETT ENGINEERING CONSULTANTS

PREPARED BY:

1000 West Nifong Boulevard, Building #1 Columbia, Missouri 65203 (573) 447-0292

www.crockettengineering.com

DAN ATWILL - PRESIDING COMMISSIONER

BRIANNA L. LENNON - COUNTY CLERK

ZONING COMMISSION THIS \_\_\_\_\_\_ DAY OF \_\_\_\_\_, 20\_\_\_

BOYD HARRIS - CHAIRPERSON

APPROVED BY THE BOONE COUNTY PLANNING AND

# FLOOD PLAIN STATEMENT:

THIS TRACT IS NOT LOCATED WITHIN THE 100 YEAR FLOOD PLAIN AS SHOWN BY BOONE COUNTY FIRM PANEL # 29019C0295E DATED APRIL 19, 2017.

### STREAM BUFFER STATEMENT:

PART OF THIS TRACT IS LOCATED WITHIN A REGULATED STREAM BUFFER AS IDENTIFIED BY BOONE COUNTY, MISSOURI. THERE SHALL BE NO CLEARING, GRADING, CONSTRUCTION, OR DISTURBANCE OF VEGETATION EXCEPT AS SPECIFICALLY APPROVED BY THE DIRECTOR.

THE PURPOSE AND INTENT OF THIS PLAN IS TO SHOW THE DEVELOPMENT OF THE

SITE INTO A BOTTLING WORKS, STORAGE AND DISTILLERY FACILITY.

# PURPOSE:

SIGNAGE: A PROPOSED MONUMENT SIGN LOCATION

2 SPACES

10 SPACES

2 SPACES

13 SPACES

41 SPACES

41 SPACES

# LEGAL DESCRIPTION:

A TRACT OF LAND LOCATED IN THE SOUTHWEST QUARTER OF SECTION 3, TOWNSHIP 47 NORTH, RANGE 12 WEST, BOONE COUNTY, MISSOURI AND BEING ALL OF THE LAND DESCRIBED BY THE TRUSTEE'S DEED RECORDED IN BOOK 3391, PAGE 178 AND BEING ALL OF THE LAND SHOWN IN THE SURVEY RECORDED IN BOOK 3373, PAGE 49 AND

### ALLOWED MODIFICATIONS:

ANY MAJOR CHANGES TO THE PURPOSE, USE AND INTENT OF THIS PLAN WILL REQUIRE A REVISED REVIEW AND FINAL PLAN TO BE PRESENTED FOR PUBLIC INPUT, EXCEPT THE FOLLOWING:

1. UTILITIES & UTILITY EASEMENTS CAN BE ADDED, REMOVED AND VACATED AS NEEDED.


# REVIEW M-LP PLAN FOR **ALLENS ORDINARY**

SECTION 3, TOWNSHIP 47, RANGE 12 COLUMBIA, BOONE COUNTY, MISSOURI OCTOBER 2022





CROCKETT JOB #190515



LEGEND:

EXISTING TREELINE

EXISTING 2FT CONTOUR

EXISTING SANITARY SEWER

MANHOLE/CLEANOUT

PROPOSED LIGHT POLE

PROPOSED FIRE HYDRANT

PROPOSED STORM SEWER

PROPOSED SANITARY SEWER

- - -820- - EXISTING 10FT CONTOUR

PROPOSED WATERLINE

EXISTING STORM SEWER

LOT NUMBER PROPOSED PAVEMENT

EASEMENT

PROPOSED STORMWATER BMP AREA

OFF-STREET PARKING REQUIREMENTS:

3,000 SQ.FT. WAREHOUSE @ 1 SPACE/2,000 SQ.FT. = 3,000 SQ.FT. MANUFACTURING @ 1 SPACE/300 SQ.FT. =

3,750 SQ.FT. WAREHOUSE @ 1 SPACE/2,000 SQ.FT. =

3,750 SQ.FT. MANUFACTURING @ 1 SPACE/300 SQ.FT. =

3,000 SQ.FT. DISTILLERY & TASTING ROOM @ 1 SPACE/300 SQ.FT. = 10 SPACES

2,400 SQ.FT. WAREHOUSE @ 1 SPACE/2,000 SQ.FT. = 2 SPACES

FUTURE BUILDING D 2,400 SQ.FT. WAREHOUSE @ 1 SPACE/2,000 SQ.FT. = 2 SPACES

OFF-STREET LOADING REQUIREMENTS:

TOTAL SPACES REQUIRED =

TOTAL SPACES PROVIDED =

MANUFACTURING OR INDUSTRIAL USE - 1 SPACE/10,000 SQ.FT.

9,750 SQ. FT. = 1 SPACES REQUIRED 2 SPACES PROVIDED

# STORMWATER CONTROL PLAN:

THIS DEVELOPMENT IS SUBJECT TO THE STORMWATER MANAGEMENT REQUIREMENTS OF THE BOONE COUNTY STORMWATER ORDINANCE. IT IS THE INTENT OF THIS DEVELOPMENT TO FULLY COMPLY WITH THE BOONE COUNTY STORMWATER REGULATIONS AND MANUAL. TO COMPLY, THIS DEVELOPMENT MAY UTILIZE BIORETENTION CELLS, RAIN GARDENS, DRY DETENTION PONDS, WET DETENTION PONDS, AND/OR OTHER APPROVED BMP'S TO MEET SAID REGULATIONS. THE CONCEPTUAL STORMWATER MANAGEMENT AREAS SHOWN ARE SIZED BASED ON PRELIMINARY STORMWATER CALCULATIONS. IF ADDITIONAL STORMWATER MANAGEMENT AREA IS REQUIRED BASED ON FINAL DESIGN, ADDITIONAL BMP'S MAY BE ADDED.

# **EROSION CONTROL PLAN:**

EROSION CONTROL FOR THIS DEVELOPMENT SHALL BE ADDRESSED BY PROPER PERMITTING AT THE TIME OF THE SUBMITTAL AND APPROVAL OF THE SITE DESIGN PLANS. ALL STATE AND LOCAL LAND DISTURBANCE AND EROSION CONTROL REGULATIONS SHALL BE ADHERED TO.

# SPILL PROTECTION NOTE:

SPILL PROTECTION FOR THE DUMPSTER AND EXTERIOR STORAGE AREAS WILL BE PROVIDED. EXACT DESIGN/CONFIGURATION SHALL BE DETERMINED DURING THE DETAILED SITE DESIGN PROCESS AND SHALL BE SUBJECT TO THE DIRECTOR OF RESOURCE MANAGEMENT'S APPROVAL.